

BULLETIN

Misc.

(07/09)

This bulletin is to make you aware of issues that have been identified by the OD or other retailers and suggest Tenant's architect and engineer pursue further as it relates to Tenant's contract documents.

- Per requirements of the building department, the barricade needs to have a hard lid..... visqueen is not permitted. Also, if there is a door in the front of the barricade, it must be a fire rated door.
- During construction, the local jurisdiction requires that either the fire sprinkler heads be turned up toward the deck and then returned to a down position upon completion of construction or the GC will need to install heat collectors on all of the heads and then remove them upon completion. Contact mall Operation's Director for details.
- Per the building department, if the tenant elects to utilize a non ducted HVAC return, then any non plenum rated cables existing in the space need to be replaced with plenum rated cables or encapsulated per the building department requirements.