

BULLETIN

Core Drilling Slab Chipping of Slab

(8/09)

Core Drilling Slab

For safety reasons, as well as to protect the integrity of the Landlord's structure, Tenants **MUST** X-ray the floor slab prior to core drilling. Tenant cannot penetrate a stem on the pre-cast.

Chipping of Slab

2" or Less – Do not need prior Landlord approval. If wire mesh is encountered, it may be cut as required. If rebars size #4 or larger are encountered, Tenant's contractor **MUST** stop work immediately and contact Landlord's structural engineer before proceeding.

Greater than 2" – Tenants must note on the floor framing plan (on Tenant's LOD) where the chipping is to take place. Tenant must also reference column gridlines. Email or fax the drawing to the Landlord's structural engineer. Review and approval from Landlord's structural engineer is at Tenant's expense.

Landlord's Structural Engineer

Steven H. Peterson, P.E.

PTAC Consulting Engineers, Inc.

880 N. Reus St., Suite 201

Pensacola, FL 32503

850.432.8446 T

850.432.9875 F

Southpark Mall
Charlotte, NC